



## Pacific Drilling Co

PO Box 84627 ph 619-294-3682  
5220 Anna Ave. Ste A f 619-294-3283  
San Diego CA 92110

[www.pacdrill.com](http://www.pacdrill.com)

### WHO WE ARE

Welcome to Pacific Drilling Company. We are a full-service drilling and soil sampling company serving the geotechnical, environmental, engineering and construction communities throughout the Southwestern United States.

Decades of leadership in limited-access drilling, combined with skilled equipment operators and a fleet of state of the art drilling rigs, both truck mount and limited access, make Pacific Drilling the reliable choice for your next drilling project.

Our services include:

- Geotechnical Sampling (all rigs)
- Large Diameter Borings For:
  - Down Hole Logging
  - Caissons
- Water/Soil Vapor Sampling
- Monitoring Well Installation
- Slope inclinometer Installation
- Grout Mixing / Pumping
- Indoor Drilling (as low as 6-ft. ceilings)
- Modular Floating Drill Platform
- Concrete Coring
- Steam Cleaning

Assisting with field investigations in difficult to reach locations is a specialty at Pacific Drilling. Our extensive experience and unique equipment capabilities enable our team to provide solutions to your project's unique challenges in a timely, cost-effective manner.

Pacific Drilling Co. is in business to provide the most skilled personnel and the most advanced equipment to ensure that your drilling, soil sampling, and related support services are delivered beyond your expectations. We approach every customer, project and job site with respect, a positive attitude, careful attention to detail and sense of pride in our work.

## Services and Equipment

### All Terrain Truck Mounted Hollowstem -Wolverine Unimog M5

4WD w/16 speed Transmission  
All Digital Hydraulic Controls  
4.25-6.25 I.D. Hollowstem Auger  
Auto SPT Hammer  
Direct Push Hammer  
Mud Rotary Drilling  
Continuous Core Soil Sampling

### Truck Mounted Bucket-Grizzly

18-42in diameter borings  
Can ream to 7ft.  
85ft depth (Before Stemming)  
150ft depth (With Stem)  
Drive samples  
Down Hole Logging

### Track Mounted Hollowstem – Mole

54 inch width clearance  
3.25/4.25 I.D. Hollowstem Auger  
Slope drilling to 2:1  
Rubber Tracks  
Continuous Core  
Angle Drilling

### Track Mounted Mini Rig – Mini Mole

36 in width clearance  
Continuous Flight Auger to 100ft  
Hollowstem Auger to 35ft  
Slope drilling to 1.5:1  
Rubber Tracks  
Angle Drilling  
Rock Drilling  
Mud Rotary

### Tripod Rig-Beaver

Slope Drilling to 1:1  
Extremely versatile  
Continuous Flight Auger to 60 ft.  
Rotary Wash

### Track Mounted Large Diameter Rig-Badger

36in width clearance  
12ft overhead  
18-30in diameter borings  
Remote Controlled  
Track Mounted (Rubber or Steel)  
40ft depth (Before Stemming)  
65ft depth (With Stemming)  
State-of-the-Art down hole logging equipment

### Certifications:

CA C-57 681380  
CA Certified Small Business  
DUNS # 613525278

(Drill Depths Subject to Soil Conditions)

	<b>Truck Mount Bucket Grizzly</b>	<b>Unimog M5 Wolverine</b>	<b>Beaver</b>	<b>Badger</b>	<b>Mini-Mole</b>	<b>Mole</b>	<b>Weasel</b>
Minimum Required Clearance	W: 24ft H: 45ft L: 35ft	W:8ft H: 30ft L: 30ft	Room to Walk	W: 36in H: 86in L: 162in	W: 36in H: 79in L: 120in	W: 54in* H: 73in L: 144in	W: 28in H: 50in L: 74in
Minimum Operating Height	45ft	35ft	96in.	144in.	132in.	108in.	86in.
Power Source	115hp Diesel	PTO	11hp Gas	38hp Diesel	33hp Diesel	67hp Diesel	PTO
Crane Weight (Heaviest Piece)	N/A	N/A	200lbs	9000lbs	4000lbs	7000lbs	650lbs
3in Solid Flight Auger	N/A	N/A	To 30ft	N/A	To 50ft	N/A	To 30ft
6in Solid Flight Auger	N/A	TBA	To 50ft	N/A	To 115ft	To 100ft	To 50ft
8in Solid Flight Auger	N/A	TBA	To 20ft	N/A	To 45ft	To 45ft	To 15ft
12in Solid Flight Auger	N/A	TBA	To 12ft	N/A	To 24ft	N/A	To 12ft
18in, 24in, 30in Boring	To 150ft***	N/A	N/A	To 65ft**	N/A	N/A	N/A
Direct Push	N/A	To 40ft	N/A	N/A	N/A	To 40ft	N/A
4in Mud Rotary	N/A	To 100ft	N/A	N/A	To 100ft	N/A	N/A
5in D.T.H. Air Hammer	N/A	TBA	N/A	N/A	To 100ft	N/A	N/A
6in Hollowstem Auger (2.75ID)	N/A	N/A	To 20ft	N/A	N/A	N/A	N/A
6.5in Hollowstem Auger (3.25ID)	N/A	To 150ft	N/A	N/A	To 35ft	To 120ft	N/A
8.5in Hollowstem Auger (4.25ID)	N/A	To 60ft	N/A	N/A	N/A	To 60ft	N/A
Angle Drill	N/A	TBA	Call Office	To 10 Degrees	To 45 Degrees	To 45 Degrees	To 10 Degrees
Maximum Slope Drill	N/A	N/A	1:1hh	2:1 (Mob Only)	1.5:1hh	2:1hh	N/A

\*\* Stemming Required from 40-65ft.

\*\*\* Stemming Required from 85-150ft.

**hh** Hillside/Hazard Surcharge Applies

Effective: 1/01/08

Description	Wolverine* (Hollow stem)	Beaver (Tripod)	Badger* (Bucket)	Grizzly* (Bucket)	Mini-Mole (Solid-Flight)	Mole (Hollow stem)
Hourly Rig Rate	2WD\$200.00*	\$155.00	\$270.00*	\$205.00*	\$220.00	\$220.00

**Additional Equipment Rates**

Core Bucket Rock Auger	N/A	N/A	\$50 Per day ea	\$50 Per day ea	N/A	N/A
Continuous Core Soil Sampling	\$200 per day	N/A	N/A	N/A	N/A	\$200 per day
Rock Drilling -Air	TBA	N/A	N/A	N/A	\$475/day	N/A
Mud Rotary/Rotary Wash	\$275/day	\$275/day	N/A	N/A	\$275/day	N/A
Auger Teeth	\$14.00 ea	\$11.00ea	\$14.00ea	\$14.00ea C4:\$22ea	\$12.00ea	\$14.00 ea
Grout Equipment, Concrete Coring, or Steam Cleaning Services	\$120 per day when accompanying drill rig otherwise, \$120.00 per day plus \$60.00 per man per hour					
Support Truck-Heavy Duty	\$250.00 per day/ \$135.00 per Half Day (5hrs)					
Support Truck-Light Duty	\$125.00 per day					
Bobcat Support for Badger	\$75.00 per day					
Exhaust Ventilation Equipment(Fan + 50ft) Additional Ducting	\$100.00 per day \$25.00 per 25ft section per day					
Interim Travel (Non Mob/DeMob)	\$150.00 per hour					
Generator	\$80.00 per day					

**Surcharges**

Overtime Surcharge	\$40.00 per man per hour
Hillside/Environmental Hazard Surcharge**	\$15.00 per man per hour
4WD/All Terrain Surcharge***	750.00 per day
Prevailing Wage Surcharge	\$37.50 per man per hour on site
Extra Man	\$60.00 per hour
Per Diem	\$115.00 per man per day

**PAYMENT TERMS:** Payment in full is due 30 days from invoice date unless otherwise agreed to writing in advance.

**MINIMUM CHARGE:** A six (6) hour minimum charge will apply to all invoices.

**CANCELLATION POLICY:** Any cancellation received less than 24 hours (1 business day) prior to scheduled rig departure will be subject to a \$750.00 charge. Jobs of two days or more are subject to a \$1250.00 charge. Jobs rescheduled within 30 days will receive a \$300.00 credit.

**OVERTIME POLICY:** Overtime surcharge will be added to the hourly rig rate:

- After 10 hours in a day
- At night (7pm-5am)
- On weekends and holidays.

\*These rigs are always accompanied by a light duty support truck, additional charges apply.

\*\***HILLSIDE/ENVIRONMENTAL HAZARD:** Projects are subject to this surcharge when **set-up** is required on hillsides or slopes steeper than 2.5:1 or on environmental jobs where hazardous materials or abnormal hazards to equipment and/or personnel exists.

\*\*\***4WD/ALL TERRAIN SURCHARGE:** Projects are subject to this surcharge whenever equipment uses 4WD to access a boring location.